



**WP SYSTEM FL**



**3 DAYS**  
100 pcs. or  
400' total

**SPECIFICATION CODE**


\_\_\_\_\_ model      \_\_\_\_\_ length      \_\_\_\_\_ voltage      \_\_\_\_\_ ballast

Model	Nominal Length	Voltage	Ballast
<b>WP-T5-S-QS</b> Standard	<b>4 - 4'</b> <b>8 - 8'</b> <sup>1</sup>	<b>120</b> <b>277</b>	<b>EB - Electronic</b> (standard)
<b>WP-T5HO-S-QS</b> Standard	<b>CR</b> <sup>2</sup> Continuous Run (runs are made up of 4' nominal fixtures unless otherwise specified)		
<b>WP-T8-S-QS</b> Standard			
<b>WP-T5-DS-QS</b> Diagonal Staggared			
<b>WP-T5HO-DS-QS</b> Diagonal Staggared			
<b>WP-T8-DS-QS</b> Diagonal Staggared			


1 8' lengths are made up with (2) 4' fixtures pre-wired from factory  
2 specify length in nominal feet

**Dimensions**


**T5/T5HO-S**



**T8-S**



**1T5/T5HO DS**



**1T8 DS**

