


Fixture Lengths

CSS-DR

Fixture Type


Approval

Continuous Run Individual Cable Centers



Fixture Length	Cable Centers (in)	Fixture Length	Cable Centers (in)	Fixture Length	Cable Centers (in)
2'	23.063"	2'	24.063"	2'	25.813"
3'	35.063"	3'	36.063"	3'	37.438"
4'	47.063"	4'	48.063"	4'	49.063"
5'	59.063"	5'	60.063"	5'	61.688"
6'	71.063"	6'	72.063"	6'	73.313"
7'	83.063"	7'	84.063"	7'	85.938"
8'	95.063"	8'	96.063"	8'	97.563"

Stand Alone Cable Centers & Overall Length




Fixture Length	Cable Centers (in)	Overall Length (in)
2'	24.625"	24.875"
3'	36.625"	36.875"
4'	48.625"	48.875"
5'	60.625"	60.875"
6'	72.625"	72.875"
7'	84.625"	84.875"
8'	96.625"	96.875"

Continuous Run Lengths and Fixture Length Segments

Nominal Length (ft)	CSS-DR Overall Length (in)	Fixture Length Segments
9	9' - 0.938"	6-3
10	10' - 0.938"	8-2
11	11' - 0.938"	8-3
12	12' - 0.938"	6-6
13	13' - 0.938"	8-5
14	14' - 0.938"	8-6
15	15' - 0.938"	8-7
16	16' - 0.938"	8-8
17	17' - 1.000"	8-6-3
18	18' - 1.000"	6-6-6
19	19' - 1.000"	8-8-3
20	20' - 1.000"	8-8-4
21	21' - 1.000"	8-8-5
22	22' - 1.000"	8-8-6

Nominal Length (ft)	CSS-DR Overall Length (in)	Fixture Length Segments
23	23' - 1.000"	8-8-7
24	24' - 1.000"	8-8-8
25	25' - 1.063"	8-8-6-3
26	26' - 1.063"	8-8-8-2
27	27' - 1.063"	8-8-8-3
28	28' - 1.063"	8-8-8-4
29	29' - 1.063"	8-8-8-5
30	30' - 1.063"	8-8-8-6
31	31' - 1.063"	8-8-8-7
32	32' - 1.063"	8-8-8-8
33	33' - 1.125"	8-8-8-6-3
34	34' - 1.125"	8-8-8-8-2
35	35' - 1.125"	8-8-8-8-3
36	36' - 1.125"	8-8-8-8-4

Nominal Length (ft)	CSS-DR Overall Length (in)	Fixture Length Segments
37	37' - 1.125"	8-8-8-8-5
38	38' - 1.125"	8-8-8-8-6
39	39' - 1.125"	8-8-8-8-7
40	40' - 1.125"	8-8-8-8-8
41	41' - 1.188"	8-8-8-8-6-3
42	42' - 1.188"	8-8-8-8-8-2
43	43' - 1.188"	8-8-8-8-8-3
44	44' - 1.188"	8-8-8-8-8-4
45	45' - 1.188"	8-8-8-8-8-5
46	46' - 1.188"	8-8-8-8-8-6
47	47' - 1.188"	8-8-8-8-8-7
48	48' - 1.188"	8-8-8-8-8-8
49	49' - 1.250"	8-8-8-8-8-6-3
50	50' - 1.250"	8-8-8-8-8-8-2



#825-00133
V-0917